



\*NOTE RE: DATA CABLES\*  
 10NO. IT SOCKETS AS SHOWN TO HAVE  
 DATA CABLE RUN TO EACH. CABLES TO  
 BE TERMINATED BY OTHERS.

3amp FUSED SPUR  
 FOR ALARM SENSOR  
 SENSOR FITTED BY OTHERS.  
 (IN 4 POSITIONS)

12192

KEY TO SYMBOLS

	Consumer Unit
	2kW Convecter Header
	Twin Skt., 300mm above F.F.L.
	5ft CAT2 Single Fluorescent Light
	Vapour Proof Fluorescent Light
	Light Switch
	External PIR Security Light
	Twin IT Socket *See Note*

FIRE ALARM SYSTEM WILL BE FITTED BY  
 A SUPPLIER AND CONNECTED ON SITE.  
 (DETAILS TO BE DETERMINED).

STEEL ANGLES TO BE FITTED TO  
 SUPPORT A CLIMBING WALL SUPPLIED  
 AND FITTED BY CUSTOMER.

ALL INTERNAL PARTITIONING TO BE STEEL  
 (FULLY WELDED) WITH PLYWOOD PANELS  
 AND INSULATION AS NORMAL.

ALL WINDOWS TO BE ALUMINIUM FRAMED  
 DOUBLE GLAZED WITH STEEL SHUTTERS.

EXTERNAL PERSONNEL DOORS TO BE  
 STEEL 90° WITH TWO LOCKING BARS.

**APPROVAL BOX**

Customer:  
 Signature:  
 Name:  
 Date:

ISSUE	DATE	DESCRIPTION
1	16/10/08	FIRST ISSUE
2	21/11/08	Customer Request: Layout Update
3	25/11/08	Customer Request: Layout Update
4	26/11/08	Customer Request: Layout Update
5	11/12/08	Customer Request: Layout Update
6	06/01/09	Customer Request: Spec. Update

LINKED USING CREAM FACED, FOIL BACKED PLASTERBOARD,  
 WITH 100mm INSULATION.  
 MONO WHITE CEILING PANELS. WHITE PLASTIC TRIM.  
 'BUBBLE WRAP' UNDERFLOOR INSULATION, WITH NON-SLIP  
 VINYL OVERLAY.

4NO. 40' x 8' OPEN PLAN OFFICE UNITS  
 LINKED & CAPPED TO CREATE A SINGLE UNIT

TITLE  
 40'x8' Linked Units  
 Open Plan Offices

**Mac Containers**

DRAWN	PB	DATE	16/10/08	DRG. No.	MAC_LX4032V01
				Sheet 1	